

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>23</u> N. R. <u>14</u> W.	L-1; K-1; k-2; K-3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-29- 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-1** Reestablished corner per standard B.L.M. instructions, which fits Manchester survey of S-1 in 1928.
- K-1** Recovered B. spike in ctr. of E-W B.top rd. which fits W.E.Manchester survey of S-1, 1928
- K-2** Restored Cor at cor.fn.post. Fn N&W, which fits survey of Sec. 1, W.E.Manchester. See recorded plat of Woodmere Subdivision, dated 1928.
- K-3** Recovered pipe in old E-W fn. per J.H. Millard survey of S-2 in 1914.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1	K-1	K-2
Set 1"x18" pipe in ctr of E-W b.top road	Fd 3/4" Boat spike	Set DNR Mon.
17" W.Pine N40E 100.1'	22" W.Pine S10E 80.8'	6" Cedar S76W 32.1'
16" W.Pine N59W 91.5'	18" W.Pine S42E 67.0'	10" Maple N 4W 54.3'
14" Maple S75W 120.0'	20" W.Pine N60E 141.0'	8" Maple N59E 31.1'
Set Ced Post w/loc tag	Set Ced.Post w/loc tag	K-3
Due N 37'	Due S 33'	Fd 1 1/2" pipe, added DNR Mon
		6" Maple N38W 17.6'
		4" W.Ash S 6W 22.0'
		10" W.Ash S78E 43.3'


SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____