

Jansing - Forestry

MANISTEE Co.

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF-: LOCATED IN-: CORNER CODE NUMBER
1. PUBLIC LAND SURVEY... T. 23 N., R. 14 W. K-5; L-5; M-4; M-5
2. PROPERTY CONTROLLING IN SECTION... T. S., R. E. W.
3. MISCELLANEOUS PROPERTY IN SECTION... T. S., R. E. W.
4. LOT NO. RECORDED PLAT
5. PRIVATE CLAIMS

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 12-26 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law.

A. Description of original monument and accessories and/or subsequent restoration:

C. Continued: M-5 Set DNR mon & Ced guard Post in approx line with irregular fn. W. 8" Maple N03E 42.9' 9" Hemlock N67W 60.0' 6" Cedar S80W 36.8' Ctr. Old N-S Rd Grade Due W 10'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-5 Recovered J.H. Millard cor & wit of rec. 1917. See large brown Co.Sur.Book Pg 193 at Register of Deeds.
L-5 Restored cor equidistant & on line between Sec. cors. E&W, which fits approx ctr of old road grade N&S and approx fence line W & approx ctr of overgrown rd grade E. in swamp.
M-4 Restored cor 33'+ E of cor fn post, Fn S&W, which fits line of fn. posts at 1/4 mile S. This position fits occupancy per survey of record by J.J.Millard in 1900 of Sec.7 (23-13). See old Co. Sur Books at Reg. of Deeds.
M-5 Restored cor 1302.2' N of Fd 1 1/2" pipe (1/16 cor of old Rec.) and on avg. line of rd S for one mile. See old Co. Sur Book large brown volume Sur. by J.H. Millard 1914 Deeds Off.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
K-5 Fd 1 1/2" pipe. Added DNR mon & Cedar Post 5" W.Pine N70E 64.3' 16" Maple S32W 29.7' 20" W Pine Stp S72W 37.9' 4" Pipe fn cor post N 5E 16.2' Ctr N-W dirt trail Due E 15'
L-5 Set DNR Mon (buried) 20" W.Pine N13E 128.5' 12" W.Pine S61E 70.2' Cor fn post N86W 25.0' Set ced post & loc tag Due W 16.5'
M-4 Set DNR Mon & Cedar gd post 14" Maple S63E 48.0' 5" Maple S41W 30.8' 9" Cedar S73W 36.1'

SIGNED BY Carl F. Roser DATE 6-15-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES: SIGNED BY CHIEF OF SURVEY PARTY DATE

APPROVED AND SIGNED BY MICHIGAN REGISTERED LAND SURVEYOR DATE

