

3EC - 1999

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION		
Manistee Located In:	Corner Code #	REGISTER'S OFFICE MANISTEE COUNTY
1. Public Land Survey T23N R 15 T 23N R 14 T R	W (A-10) V	99-333at-4135pm SEP 29 1999
2. Property Controlling S T R in Section S T R		REGISTER OF DEEDS
3. Miscellaneous       S T R         Property in Sec S T R		Register of Deeds Stamp & File Number A B C D E F G H I J K L M
4. Lot No, Recorded Plat 5. Private Claims		
I Design I language in a field of		4 - 7 - 8 - 9 - 10 - 11 - 12 - 5
I, <u>Bruce J. Jenema</u> , in a field survey on <u>April 27</u> , 19 <u>99</u> do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:		6 -18 - 17 - 16 - 15 - 14 - 13 - 7 8 - 19 - 20 - 21 - 22 - 23 - 24 - 9 10 - 30 - 29 - 28 - 27 - 26 - 25 -
NOTE: Not more than 2 corners, all in the same on this certificate.	town and range, may be recorded	11 12 31 32 33 13 F Mid 35 36
A. Description of original monument and accessories and/or subsequent restoration:  BRUCE J.		
12\ onesign /256		12\ 0100EV00 /2F9/0
1838 J. Brink, D.S., GLO Set post 1.) 11" Beech S81°W 46 links (30.36') 2.) 11" Sugar N36°W 8 links (5.28')	1901 J.H. Millard, D.S. Recorded C.S. Bk A, pg 222 & Bk B, 3.) School pump N57°W 124 lks (81 4.) Cedar F.P. S2°W 38 lks (25.08')	
1902 H. Knight, C.S. Recorded in C.S. Book B, page 156-157	1906 J.J. Hubbell, Jr., C.S. Rec in C.S. Bk A, pg 209 & Bk B, pg Found old post by Knight 5.) SE cor School House N64°W 152 6.) 10" T. Pole S81°E 188 links (124	the Manister of Transfer of Tr
DATE/SURVEYOR UNKNOWN Manistee Co. Road Commission corner records 7.) T. Pole NE 65.1' 8.) T. Pole NW 70.2'	USGS BM button on	1. I'b' State Surve
9.) Fence Post S 35.35'		Our the first th
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  On April 25, 1999, I found a 1" iron pipe 8" below the road surface. Corner is in the center of East-West and North Road.		
On April 25, 1999, I found a 1" iron pipe 8" below the road surface. Corner is in the center of East-West and North Road.  No conflicting evidence of other corners existing.		
1.), 2.), 3.), 4.), 5.), 6.), 7.), 8.), 9.) are now extinct  Note: Witness # 5, there is no evidence of Old school building, yard or fences.		
C. Description of monument for corner and	accessories established to perpe	stuate locating the position of the corner:
On July 14, 1999, I found a 1" iron pipe and place of said 1" iron pipe and is accepted as the best a		
10.) N06°W P.Pole 184.31 ' Set 60-D East side 12.) N50°E 10" R. Pine 95.65' Set 60-D E. side 14.) N65°W 20" tw. Walnut 170.30' Center N	13.) S30°W Face	pole 189.70' Set 60-D W. side c of Vent pipe for gas pipeline 31.50' R. Pine 138.65 Set 60-D S. side
Signed by Brusse f. Jenuma Surveyor's Michigan License No. 25850		16-49
Surveyor's Michigan License No. 25850		