

OCT 03 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 24N R 14W K-13
2. Property Controlling in Section S T R NE Sec Cor
3. Miscellaneous Property in Sec. S T R Sec 2
4. Lot No. , Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY
00-300 at 11:35 p.m.
SEP 03 2000
Penny A. Repna
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on June 23, 20 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column K and row 1.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Southeast Section Corner Section 35 (24-14) & Northeast Section Corner Section 2 (23-14) Set by John Brink in 1837.

- 1. Black Ash 11" in dia. N 36° E 18 links (11.88')
2. Black Ash 13" in dia. N 80 1/2° W 23 links (15.18')

DNR Map of part of T24N, R14W (includes Section 35)
Found Boat Spike, no witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Southeast Section Corner Section 35 (24-14) & Northeast Section Corner Section 2 (23-14)
On June 23, 2000, I, Anthony Slawinski, along with a field crew, found a Cabin spike in the centerline of 13 Mile Road, 33' North of DNR location post. We found no other evidence to dispute this location for the corner.

Condition of witnesses: #1 gone, #2 gone

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Southeast Section Corner Section 35 (24-14) & Northeast Section Corner Section 2 (23-14)

On June 23, 2000 I set a Manistee County Monument in a monument box in the exact location as the above mentioned Cabin spike as a careful and faithful re-establishment of the position of the original corner, and witnessed by:

- 3. S 40° E 67.50' 24" White Pine (fd. 40d flush with bark)
4. S 07° E 81.47' 30" White Pine (set 40d west side of tree)
5. N 09° W 40.18' 6" Maple Clump (set 40d on east side of tree)
6. S 38° W 44.94' 6" White Pine (set 40d on west side of tree)

Found DNR post 33' south of corner.
Corner is in centerline of 13 mile road.

Corner K-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq. ). Date of Peer Review: 7-31-00

Anthony M. Slawinski



Signed by Anthony M. Slawinski
Surveyor's Michigan License No. 13597

Date 7-26-00