

**SURVEY & REMONUMENTATION**

DEC 09 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MANISTEE Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 23 N R 14 W M-8  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**REGISTER'S OFFICE  
 MANISTEE COUNTY**  
 99-250 at 4:10pm  
**AUG 12 1999**  
*Deborah Six*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

I, Sammy S. Barnett, in a field survey on June 14th 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 M - 8 East one-quarter corner of section 24 T23N, R14W

- |   |   |
|---|---|
| 1838 GLO survey by John Brink, set post | 1986 survey by A.M. Slawinski, found PK nail, replaced with 1/2" I.R. |
| # 1 Hemlock 12" S30W 31 lks (20.46')    | # 3 R. Pine 12" N30W 51.74'   |
| # 2 Ironwood 7" N23W 27 lks (17.82')    | # 4 P.P. N30E 84.56'  |
|   | # 5 Tel. box marker 4x4 S30W 65.17'                                   |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

M - 8 East one-quarter corner of section 24 T23N, R14W  
 On July 7th 1999, I found the 1/2" re-bar reset by A. Slawinski, 15' S. of a 2 track rd. to the West & 1' E. of centerline of blacktop North and South. Condition of the witnesses are as follows,  
 Gone # 1 & # 2 found in good condition # 3, # 4 & # 5

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

M - 8 East one-quarter corner of section 24 T23N, R14W  
 On July 7th 1999, I accepted the found 1/2" rebar as the best available evidence of the position of the original corner, and replaced it, in the exact location, with a standard Manistee Co. Mon., stamped to identify the corner, in a mon. box, and took the following witnesses.  
 # 3 R. Pine N40W 51.55' set 60d spike in SW side  
 # 4 Power pole N34E 84.52' fd. nail & gear in SE side  
 # 5 Tel. box marker 4 x 4 S30W 65.17' fd nail in NW side  
 # 6 Wood stop sign post S78E 20.65' set nail in S. side

Corner M-08 ratified by the Manistee County Peer Group  
 according to the county plan adopted pursuant to P.A. 345 of 1990,  
 as amended, (being the State Survey and Remonument Act, MCL 54.261  
 et seq.). Date of Peer Review: Anthony M. Slawinski

AUG 03 1999

Signed by Sammy S. Barnett Date 8/1/99

Surveyor's Michigan License No. PS # 16923

