

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____
 Manistee _____
 (County)

Located In _____
 Corner Code # _____

- | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>23N</u> | R | <u>14W</u> | <u>H2</u> |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | <u>3</u> | T | <u>23N</u> | <u>14W</u> |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on June 25, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | | | 5 | | 4 | | 3 | | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- H2 - 1914 - CSR - L. 'A', p. 194 - E. W. Muenschler 8 - None
 1) Hem. Stump 40" N84°W 29 L.
 2) Poplar 2"



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H2 - C 1/4 Corner, Sec. 3 - No conclusive evidence of 1914 position found. Set 2" Alum. Cap on 5/8" x 34" rebar at intersection of 1/4 lines per Standard BLM procedure. Corner in line with old field furrow to east. Fits centerline of overgrown 2-track N & S which is consistent with corner 'H3' being in line with 2-track going North. Remains of a N-S Lane fence is 23'± West.
- 8 - CW 1/16 Corner, Sec. 3 - Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM Procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H2 - Stamped 2" Alum. Cap on 5/8" x 34" rebar.
 Set Blue Carsonite Post with loc. tag 1' NE
 S25°E 36.73' to set N & T in SW side 16" R. Pine scribed 'XBT'
 N33°E 26.28' to set N & T in SW side 18" R. Pine scribed 'XBT'.
 N20°W 52.36' to set N & T in E. side Tw. 12" Cherry
 S35°W 59.95' to set N & T in SE side 6" Cherry
- 8 - Stamped 2" Alum. Cap on 5/8" x 34" rebar.
 Set Blue Carsonite Post with loc. tag 1' West
 N5°W 23.42' to set N & T in NE side 4" J. Pine
 S75°E 43.38' to set N & T in SW side Tw. 10" Cherry
 N77°W 12.34' to set N & T in N. side 4" J. Pine
 South 18.59' to set N & T in E. side 3" J. Pine

Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 6/28/2010