

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Manistee (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	T _____ R _____	_____
	S <u>3</u> T 23N R 14W	<u>4</u>
	S <u>3</u> T 23N R 14W	<u>5</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____


I, Craig W. McVean, in a field survey on April 21, 2008 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1								●					
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

4 - None 5 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

4 - NW 1/16 Corner, Sec. 3 - Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. 5 - CN 1/16 Corner, Sec. 3 - Set 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure. Corner falls in swampy hardwoods.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>4</u> - Stamped 2" Alum. Cap on 5/8" x 34" rebar. Set Blue Carsonite Post with loc. tag 1' NW N22°W 21.48' to set N & T in SW side 13" Tw. Cherry N43°E 66.11' to set N & T in NW side 14" R. Pine S40°W 21.17' to set N & T in NW side 13" Tw. Cherry S23°E 81.02' to set N & T in E. side 6" J. Pine</p>	<p><u>5</u> - Stamped 2" Alum. Cap on 5/8" x 34" rebar. Set Blue Carsonite Post with loc. tag 1' N N42°E 29.42' to set N & T in NW side 12" Cedar N25°W 15.86' to set N & T in W. side Tw. 12" & 10" R. Maple N85°W 21.96' to set N & T in S. side 5" Y. Birch S44°E 0.58' to set N & T in N. side 9" R. Maple</p>
--	--

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 6/28/2010