

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In: <u>15 W</u>	Corner Code #
1. Public Land Survey	T <u>23NR</u> T <u>15</u> T <u>17W</u>	Closing <u>A-02 W 1/4 cor. Sec. 6</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTER'S OFFICE
MANISTEE COUNTY
98-375 at 10:40AM
SEP 17 1998
Detmehdix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Bruce J. Jenema, in a field survey on August 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1837 John Brink 40 ch set post
 (1) Hemlock 12° N79°W 7 links (2) 12° Hemlock S19°W 41 links (now extinct)
 12/7/1914 E.W.M. Set stone

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron & cap #25869 Established by James Ray July 19, 1989, for corner the W 1/4 of Sec. 6, T23N, R15W, using E.W.M. record 12/7/1914 and witnessed by:
 (3) East 33' 1/2" iron
 (4) N40°W 65.50' 16" W. Pine
 (5) N70°W 53.68' 10" R. Pine
 2/12/97 Daniel Schripsema #24617 used this corner for the E 1/4 corner, Sec. 1, T23N, R16W and witnessed by:
 (4), (5)
 (6) East 28.58' P. pole
 (7) N40°E 95.82' 8" W. Pine
 The occupation for this corner is both East & West

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 On August 1, 1998, I found a 1/2" x 18" iron and placed a standard Manistee County Monument in the exact location of the 1/2" x 18" iron as the best available evidence of the location to re-establishment of this corner and witnessed by:
 (3) East 33.00' 1/2" iron
 (4) N40°W 65.50' 16" W. Pine 60-D S. side
 (5) N70°E 53.68' 10" R. Pine 60-D S. side
 (6) S85°E 28.58' P. pole 60-D N. side
 (7) N40°E 95.82' 8" W. Pine 60-D S. side
 (8) West 33.00' 1/2" iron
 (9) South 11.40 W 1/4 cor. Section 6, T23N, R17W

Corner A-02 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Slawick
AUG 04 1998

Signed by Bruce J. Jenema
 Surveyor's Michigan License No. 25850

Date Aug 3 1998

