

SURVEY & REMONUMENTATION

JAN 21 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee  
(County)

Located In:

Corner Code #

1. Public Land Survey	T	23N	R	15W	A-03	<i>Closing</i>
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T	R		
	S		T	R		
3. Miscellaneous Property in Sec.	S		T	R		
	S		T	R		

SECTION REGISTER'S OFFICE  
MANISTEE COUNTY

# 97-310 A+A:30 A.N.  
AUG 21 1997

*Penny A. Peters*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Bruce J. Jenema, in a field survey on May 01, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-03closing SW Sec. 6, T23N R15W  
James Highbee 1839 81.22 chains intersect W. Boundary 36 links (23.76') North of post witnessed by  
(1) 12" Beech N15°E 36 links (2) 12" Beech S45°E 40 links

Note: GLO map does not indicate a closing corner at this point.

EWM found stone for Sec. cor. between 1 & 12, T23N, R14W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x30" iron pipe at the intersection of the centerlines of Potter & Milarch Road.


LCRC #76-3 H.R. Bruning

(3) 7" R.Pine N30°E 110.95' (4) 4" J. Pine S64°E 74.34'

(5) 24" Maple N80°W 122.46'

Certificate of survey by Ken Ross recorded Liber 2, page 635 of surveys.

By extending West, the South line of the Plat of Wildwood which is along the South line of the SW 1/4 of Sec.6, T23N, R15W Falls 5 ft. North of this corner position.



ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1993, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: May 6, 1997  
*Anthony M. Skowich*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 06, 1997, I installed a Manistee County Monument, within a monument box in the exact location of the above 1" iron pipe and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:

(6) 14" R.Pine N30°E 110.31' 60-D spike N.side (7) 8" Maple N40°W 64.95' 60-D spike N.side

(8) 4" J.Pine S50°E 87.57' 60-D spike N.side (9) U.Pole S08°E 180.5' 60-D E.side

Signed by *Bruce J. Jenema*  
Surveyor's Michigan License No. 25850

Date May 02, 1997