

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Manistee  
(County)

Located In:

Corner Code ##

- |                                    |   |            |   |            |                    |       |
|------------------------------------|---|------------|---|------------|--------------------|-------|
| 1. Public Land Survey              | T | <u>23N</u> | R | <u>15W</u> | <u>A-04closing</u> |       |
|                                    | T | _____      | R | _____      | _____              |       |
|                                    | T | _____      | R | _____      | _____              |       |
|                                    | T | _____      | R | _____      | _____              |       |
| 2. Property Controlling in Section | S | _____      | T | _____      | R                  | _____ |
|                                    | S | _____      | T | _____      | R                  | _____ |
| 3. Miscellaneous Property in Sec.  | S | _____      | T | _____      | R                  | _____ |
|                                    | S | _____      | T | _____      | R                  | _____ |

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 #97-256 AT 11:13 A.M.  
**JUL 25 1997**  
*Permy A. Regina*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Bruce J. Jenema, in a field survey on May 01, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-04 closing W $\frac{1}{4}$  Sec. 7, T23N, R15W  
 This corner was not established by G.L.O.

**SURVEY &  
 REMONUMENTATION**  
  
**OCT 14 1997**  
  
**COMMISSION**


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L.C.R.C. #76-03 H.Bruning Set 5/8" iron from Road Commission witnesses and made the following witnesses:  
 (1) 8" Apple NE 94.11' (2) 8" Apple ENE 74.18' (3) 6" J.Pine West 61.53'  
 (1) & (2) exist however no markings were on the Apple trees (3) Found stump  
 Certificate of survey recorded Liber 2 of surveys page 635, Feb. 1996,  
 by Ken Ross, also indicates acceptance of this corner by Anthony Slawinski.

Corner A - 04 c ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Slawinski  
MAY 16 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 02, 1997, I installed a Manistee County Monument, within a monument box in the exact location of the above 5/8" iron and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner and witnessed by:  
 (1) (2) & (3) remain in place  
 (4) 30" Maple S05°E 179.46' 60-D spike N.side  
 (5) 6" Cedar S64°E 49.85' 60-D spike N.side  
 (6) Wooden gate post N90°W 33.95' 60-D N.side



Signed by Bruce J. Jenema  
 Surveyor's Michigan License No. 25850

Date June 2, 1997