

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER'S OFFICE
MANISTEE COUNTY
 # 97-853 at 11:05 A.M.
JUL 25 1997
Penny A. Repasa
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in
Manistee
 (County)

Located In: Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|---------------|
| 1. Public Land Survey | T | <u>23N</u> | R | <u>15W</u> | <u>A-05 c</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema, in a field survey on May 02, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-05 closing SW Sec. 7 T23N, R15W
 James Highbee 1839 81.90 chains intersect West boundary of Township 28 links (18.48) North of Post corner between 7 & 18
 (1) sugar 14" S17°E 54 links (2) sugar 14" N00°E 83 links
 NOTE: G.L.O. maps do not reflect standard closing corners at this point
 June 1893 EWM Notes 18 2/3' North of NE corner, Section 13, T23N, R16W, Bk A, page 234

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 60-D spike
 Standard corner between Sections 12 & 13, T23N, R16W, is South 18.66 ft.

SURVEY &
REMONUMENTATION
 OCT 14 1997
 COMMISSION

Corner A-05 c ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review MAY 6 1997
Anthony M. Shanks

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 02, 1997, I installed a Manistee County Monument, within a monument box in the exact location of the above, 60-D spike and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:
 (3) 8" Cottonwood N50°W 39.50' 60-D spike S.side
 (4) 8" B.Locust N62°E 69.78' 60-D spike S.side
 (5) 14" Cottonwood S25°E 76.45' 60-D N.side
 (6) P.pole S62°W 54.70' 60-D spike S.side



Signed by Bruce J. Jenema
 Surveyor's Michigan License No. 25850

Date May 02, 1997