

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Manistee  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 23N R 15W A-06closing  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 #97-254 at 11:08A.m.  
**JUL 25 1997**  
*Penny A. Repora*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Bruce J. Jenema, in a field survey on May 02, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-06 CLOSING W 1/4 Sec. 18, T23N, R15W

This corner was not established by the General Land Office.

Manistee County survey records, page 220. Found Stone. Sept. 1987 JHM  
 Also EWM found stone May 1915, Book "A", page 234.

**SURVEY &  
 REMONUMENTATION**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

OCT 14 1997

COMMISSION


H.R. Bruning 1975 survey recorded Liber 1, page 283-284.  
 H.R. Bruning L.C.R.C. #76-03  
 (1) 30" Maple N90°E 92.31' (2) P.Pole S10°W 157.62'  
 (3) 16" Walnut N70°W 51.00'

On April 28, 1997, I found H.R. Brunings 5/8" iron & cap also witness #3 in good condition and the stump of #1.

Standard corner E 1/4 Section 13, T23N, R16W 18.33'

Corner A - Q E C ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: Anthony M. Naurachi

MAY 6 1997



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 On May 02, 1997, I installed a Manistee County Monument, within a monument box in the exact location of the above 5/8" iron and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner and is witnessed by:

(3) 16" Walnut N70°W 51.00' (4) 12" Cottonwood S30°E 59.00'  
 (5) SE corner dwelling N42°W 76.38' (6) 12" Cottonwood S68°E 37.18'

Signed by Bruce J. Jenema  
 Surveyor's Michigan License No. 25850

Date May 02, 1997