

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code # (closing)
1. Public Land Survey T 23NR15W A-10c W 1/4 Sec. 30
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REGISTER'S OFFICE MANISTEE COUNTY
98-377 at 10:50 am
SEP 17 1998
Deborah Six REGISTER OF DEEDS

4. Lot No. Recorded Plat
5. Private Claims

I, Bruce J. Jenema, in a field survey on July 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number
Grid with columns A-L and rows 1-13. Cell 10,3 contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:
This corner was not established by the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
This corner was established by the mean of closing distances of 16.5 ft. at the Southeast corner of Section 25 and 19.88 ft. at the Northeast corner Section, and established distance of 18.19 ft. North of the E 1/4 corner of Section 25 and on a line with the Northwest corner of Section 25.
This corner was not used as a property control corner and is in conflict with occupation which is South 18 ft., a tree and fence line running East.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
On August 1, 1998, I placed a standard Manistee County Monument as the position of this corner by measuring 18.19 ft. North along the West line of Section 30 from the East one-quarter of Section 25, T23N, R16W, as best available evidence of the position of this corner and witnessed by:
S65°E 46.32 ft. P. pole 60-D N. side (1)
N45°E 24.29 ft. Face MBT Jct. box (2)
N02°W 52.15 ft. 8" Cottonwood 60-D E. side (3)
S40°E 97.64 ft. Tw. 8' & 12" R. Pine 60-D N. side (4)
South 18.19 ft. E 1/4 corner of Sec. 25 (5)
This corner has not been accepted as a property control corner, occupation is 18' South running East.

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date 04-08-98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197

Corner A-10C ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Sawinski
AUG 4 1998



REVISED MAY 14, 197
REVISED JAN., 1983
REVISED OCT., 1995