

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Manistee  
(County)

Located In: \_\_\_\_\_ Corner Code ##

- |                                    |   |            |   |            |               |
|------------------------------------|---|------------|---|------------|---------------|
| 1. Public Land Survey              | T | <u>23N</u> | R | <u>15W</u> | <u>A-11 c</u> |
|                                    | T |            | R |            |               |
|                                    | T |            | R |            |               |
|                                    | T |            | R |            |               |
| 2. Property Controlling in Section | S |            | T | R          |               |
|                                    | S |            | T | R          |               |
| 3. Miscellaneous Property in Sec.  | S |            | T | R          |               |
|                                    | S |            | T | R          |               |

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 #97-257 at 11:15 A.M.  
**JUL 25 1997**  
*Arroyo A. Rivera*  
**REGISTER OF DEEDS**

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema in a field survey on May 1, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**A-11 closing SW Sec. 30, T23N R15W**  
**James Highbee 1839 80.53 chains intersect West boundary 25 links North of corner post**  
**Section 30 & 31, 23-16 Witness:**  
**(1) 14" Beech N32°W 43 links (2) 12" Beech S34°E 20 links**


**SURVEY & RE-MONUMENTATION**  
**OCT 14 1997**  
**COMMISSION**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**July 1903 J.H. Mallard Book "B", page 172. Found iron point a little South of crossroads.**

**On May 1, 1997, I reestablished the above corner, 25 chains (16.5') North of the Northeast corner of Section 36, T23N, R16W.**

Corner A-11 c verified by the Manistee County Peer Group according to the county records pursuant to P.A. 345 of 1990, as amended, (being the Surveyors' Amendment Act, MCL 54.261 et. seq.) Date of Peer Review: MAY 10 1997  
*Anthony M. Slawinski*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**On May 02, 1997, I installed a Manistee County Monument at the above reestablished location, within a monument box and accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:**

- (3) 1.5' sq. concrete marker SE corner N50°W 39.7' (4) U.Pole S25°W 79.6' Found #16 spike/washer (5) 14" Elm S08°E 105.4' 60-D spike N.side (6) SE corner Brick house N65°W 158.2'**

Signed by Bruce J. Jenema Date May 02, 1997  
 Surveyor's Michigan License No. 25850