

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Manistee  
(County)

Located In: 23N 15W Corner Code #  
A-12  
(W 1/4 Sec. 31)

1. Public Land Survey T      R       
T      R       
T      R       
T      R     

2. Property Controlling S      T      R       
in Section S      T      R     

3. Miscellaneous S      T      R       
Property in Sec. S      T      R     

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**

# 97-308 AT 9:10 A.M.  
**AUG 21 1997**

*Penny A. Peters*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Bruce J. Jenema, in a field survey on June 2, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													


A. Description of original monument and accessories and/or subsequent restoration:

A-12 W 1/4 Section 31

**This corner was not established by the US Government G.L.O. surveyors**  
**SURVEY &**  
**REMONUMENTATION**

**OCT 14 1997**

**COMMISSION**



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 W 1/4 Section 31

On April 1, 1997, I didn't find a corner marker at this location. A tree row & a dead furrow (occupation) is running East from this location, I established the location of this corner 8.25' North of the East one-quarter of Section 36, T23N, R16W, on the West line of said Section 36 which is the calculated dimension from G.L.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On June 30, 1997, I installed a Manistee County Monument, within a monument box in the exact location as determined in part "B" above and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner and is witnessed by:

- (1) 16" W.Pine N90°E 50.10' Found #16 Duplex S.side
- (2) Gate post S65°E 39.85' (3) 12" Maple N50°W 67.10 ft.
- (4) NE corner of Telephone equipment box S45°W 61.00'
- (5) Standard corner W 1/4 corner Section 36, T24N, R15W 8.25' South

Signed by Bruce J. Jenema Date June 30, 1997  
Surveyor's Michigan License No. 25850

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, being the State Survey and Remonument Act, MCL 56.261 et seq. Date of Peer Review: July 1, 1997

*Anthony M. Slavick*