

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Manistee

(County)

Located In:

Corner Code #1

1. Public Land Survey

~~T 23N R 16W M-13 SE Sec. 36~~

~~T 23N R 16W M-13~~

T 23N R 16W M-13

2. Property Controlling  
in Section  
3. Miscellaneous  
Property in Sec.

S T 23N R 16W  
S T 23N R 15W  
S T 23N R 15W  
S T R

M-13  
A-1  
A-13

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**

96-467 at 3:30pm  
**OCT 16 1996**

*Keborah Six*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Bruce J. Jenema, in a field survey on September 5, 1996

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-13 SE corner Section 36, T23N, R16W  
John Brink Deputy Surveyor Dec. 25, 1837  
(1) 16" Sugar S14°E 19 links (2) 10" Sugar N18 1/2°W 34 links  
1903 J.H. Millard (Book B page 172) Found point of decayed stake set iron & stone  
(3) 8" Sugar S86°E 48 links (4) 8" Sugar S15°W 67 links  
7/12/1976 Certificate of survey Northwest Survey & Engineering Co.  
Found nail for SW corner Sec. 31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found on September 6, 1996, I found 5/8" iron w/ ID cap (illegible)



Corner M-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monument Act, MCL 54.261 et seq.). Date of Peer Review: SEP 17 1996

*Anthony M. Stamm*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On September 9, 1996, I installed a Manistee County Monument, within a monument box in the exact location of the above 5/8" iron rod and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:  
(5) P.Pole N24°E 169.59' Fnd. (6) 10" Beech S17°E 101.10' Fnd.  
(7) Group of 3" Cherrys N25°W 76.80' Fnd. (8) 6" Apple N86°W 35.15' Set

Signed by Bruce J. Jenema  
Surveyor's Michigan License No. 25850

Date September 5, 1996