

SURVEY &
RECORDATION

OCT 31 1994

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>23N</u> R <u>15W</u> | <u>C-03</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

REGISTER'S OFFICE
MANISTEE COUNTY

#94-321 AT 4:55 p.m.

JUL 11 1994

Pemsey A. Peper
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3		●								
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					
13										

I, Anthony M. Slawinski in a field survey on June, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-03 SE cor sec 6 T23N R15W
1839 James Higbee D.S. G.L.O. Page 235.
Set post cor to sec's 5-6-7 & 8

Manistee County Road Commission
3/4" iron rod

- | | |
|------------------------------------|-----------------------|
| #1 Beech 10" N63°W 43 lks. (28.38) | #3 NW 44.1 22" Maple |
| #2 Beech 12" S81°E 64 lks. (42.24) | #4 NE 45.5 20" Walnut |
| | #5 SW 42.6 21" Maple |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-03 SE cor sec 6 T23N R15W
On June 30, 1994 found P.K. Nail, under P.K. nail found a 3/4" iron rod 18" long.

Condition of record witnesses are; #1, #2, #4 are gone
#3 and #5 are in fair condition.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-03 SE cor sec 6 T23N R15W

Replaced P.K. nail with a Manistee County monument placed in a monument box, and is accepted as a careful and faithful reestablishment of the position of the original cor.

- N35°W 56.65 09" Fir
- N60°W 45.23 24" Maple.
- S60°W 43.44 24" Maple
- N53°E 62.05 29" Maple

Signed by Anthony M. Slawinski
Surveyor's Michigan License No. 13597

Date June 30, 1994



ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Reorganization Act, MCL 54.261 et. seq.) . Date of Peer Review: August 1, 1994 *Anthony Slawinski*