

OCT 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County)	Located In:	Corner Code #
1. Public Land Survey	T 23N R 15W	C-04
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER'S OFFICE
MANISTEE COUNTY
#94-320 AT 4:50 p.m.
JUL 11 1994
Penny A. Peters
REGISTER OF DEEDS

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J
2	6		5		4		3		2	
3										
4	7		8		9		10		11	
5										
6	18		17		16		15		14	
7										
8	19		20		21		22		23	
9										
10	30		29		28		27		26	
11										
12	31		32		33		34		35	
13										

Anthony M. Slawinski in a field survey on June 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-04 E 1/4 corner sec 7 T23N R15W

1839 James Higbee D.S. G.L.O. Page 235
Set 1/4 sec post on sec line

Manistee County Road Commission

- #1 Sugar 18" East 8 lks (5.28')
- #2 Sugar 12" S55°W 30 lks. (19.80')

- #3 SW 39.55' 36" Maple
- #4 NW 45.27' 36" Maple
- #5 SSW 59.30 30" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-04 E 1/4 corner sec 7 T23N R15W

On June 30, 1994 found 3/4" iron rod, under iron rod found stove grate. Condition of record witnesses are; #1 and #2 are gone, #3, #4 and #5 found in good condition.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-04 E 1/4 corner sec 7 T23N R15W

Replaced 3/4" iron rod with Manistee County Monument placed in a monument box, and is accepted as a careful and faithful reestablishment of the position of the original corner.

- (OBT) #3 S65°W 39.55' 36" Maple
- (OBT) #4 N52°W 45.27' 36" Maple
- (OBT) #5 S39°W 59.28' 30" Maple
N21°W 87.37' 29" Ash

ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261)

C-04
Corner

Signed by *Anthony M. Slawinski* Date June 30, 1994
Surveyor's Michigan License No. 13597

