

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>15W</u>	<u>D-05</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER'S OFFICE
 MANISTEE COUNTY

#94-347 AT 9:50 A.M.

AUG 2 1994

Penny A. Repore
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Anthony M. Slawinski, a field survey on June 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-05 S $\frac{1}{4}$ cor sec 8	T23N R15W	Manistee County Road Commission
1839 James Higbee D.S. G.L.O. page 234		1" iron pipe flush w/surface
Set 1/4 sec post on sec's 8 & 17		#3 SE 40.38' 16" Apple
#1 Sugar 14 N10W 44 lks (29.04')		#4 SE 24.83' 20" apple
#2 Beech 24 S12°E 50 lks (33.00')		#5 SW 50.09' Guy Pole
		#6 NW 58.15' Tele. pole
		#7 NE 61.60' Guy pole
		#8 South 39.69' Fence Post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-05 S $\frac{1}{4}$ cor sec 8	T23N R15W	On Jan. 6, 1976, James T. Nordlund filed Act 74 L 76 P 01 SET 1/2" Re-bar midway between SW & SE section corners.
On June 30, 1994 found cabin spike, under spike found another spike.		#9 SW Fence post 33.74'
Condition of record witnesses are;		#10 Due S Power pole 92.49'
#1 thru #7 Gone #9 & #11 Gone		#11 SE Stop ahead sign N. leg 99.06
#8 Fair, #10 Good.		

Corner D-05 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Barry J. Jensen
 ACTING CHAIRMAN **APPROVED AUG 1 1994**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-05 S $\frac{1}{4}$ cor sec 8 T23N R15W
 Replaced cabin spike with Manistee County Monument, placed in a monument box and is accepted as a careful and faithful reestablishment of the position of the original cor

(O.B.T.) #10 S09°E 103.35' power pole
 (O.B.T.) # 8 S03°W 39.12' Fence cor. post
 S57°E 71.94' Cedar fence post
 N79°W 238.40' power pole



Signed by Anthony M. Slawinski Date June 30, 1994

Surveyor's Michigan License No. 13597