

SURVEY & REMONUMENTATION

OCT 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>23N</u> R <u>15W</u>	<u>D-07</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER'S OFFICE
MANISTEE COUNTY
#94-316 AT 4:10 p.m.
JUL 1 1 1994
Penny A. Repner
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Anthony M. Slawinski in a field survey on July 1, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-07 S $\frac{1}{4}$ cor sec 17 T23N R15W

1839 James Higbee D.S. G.L.O. Page 233
Set 1/4 sec post sec's 17 & 20

#1 Hem 12 S12°E 9 lks (5.94')
#2 Hem 10 N70°W 14 lks (9.24')

On June 1, 1973 Ken Ross filed Act 74 L-73 P-17 Found 1" iron

#3 14" Elm S50°W 43.31'
#4 6" cherry NNE 19.17"
#5 Hwy. Center line East 116.0'
#6 centerline Hwy R/W Monument SE 34.2'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-07 S $\frac{1}{4}$ cor Sec 17 T23N R15W

On July 1, 1994 found 1" iron under iron found crockery.

Condition of record witnesses are; #1 thru #3 Gone
#4, #5 and #6 Good.

Corner D-07 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: _____ CHAIR
APPROVED JUL 1 1 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-07 S $\frac{1}{4}$ cor sec 17 T23N R15W

Replaced 1" iron with Manistee County Monument placed two inches above surface and is accepted as a careful reestablishment of the position of the original cor.

(OBT) #6 S08°E 34.16' top center conc. R/W Marker
(OBT) #4 N18°E 19.22' 12" cherry.
N78°E 24.42' 6" Ash.
S42°W 33.56' 6" Elm.



Signed by Anthony M. Slawinski Date July 1, 1994
Surveyor's Michigan License No. 13597