

SURVEY &
REMONUMENTATION
OCT 31 1994
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Manistee</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 23N R 15W	E-06
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER'S OFFICE
MANISTEE COUNTY
#94-314 AT 3:25 p.m.
JUL 11 1994
Penny A. Peters
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K
2	6		5		4		3		2		
3											
4	7		8		9		10		11		
5											
6	18		17	●	16		15		14		
7											
8	19		20		21		22		23		
9											
10	30		29		28		27		26		
11											
12	31		32		33		34		35		
13											

Anthony M. Slawinski in a field survey on July 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


E-06 E1/4 cor sec 17 T23N R15W
1839 James Highbee D.S. G.L.O. Page 228
40 chains North of SE cor 10" Maple on line
"No Witnesses"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-06 E1/4 Cor sec 17 T23N R15W
On July 1, 1994 found 1/2" iron pipe alongside
of 2 steel fence posts.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-06 E1/4 cor sec 17 T23N R15W
Replaced the 1/2" iron pipe with a Manistee County Monument 2 inches above surface and is accepted as a careful and faithful reestablishment of the position of the original corner.
S01°W 41.17' 8" Elm
S58°W 23.52' 8" Maple
N18°E 29.34' 18" Maple
N16°W 39.75' 20" Maple

Corner E-06 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: July 1, 1994
APPROVED JUL 11 1994


Signed by Anthony M. Slawinski Date July 1, 1994
Surveyor's Michigan License No. 13597