

SURVEY & REMONUMENTATION

DEC 7 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970


For corners in SECTION

Manistee Located In: Corner Code #
1. Public Land Survey T 23N R 15W M-06 E 1/4 cor. Sec. 13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY
99-332 at 4:30pm
SEP 29 1999
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 and some symbols.



I, Bruce J. Jenema, in a field survey on April 27, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-06 T23N, R15W, (E 1/4 cor. Sec. 13) Common to A-06 T23N, R14W

1838 J. Brink, D.S., GLO
Set Post

- 1.) 40" Hemlock S35°W 29 links (19.14')
2.) 20" Hemlock N56°W 10 links (6.60')

1899 J.H. Millard

Found Hemlock stump marked & stake
Set stove leg & top

- 2.) 40" Hemlock stump N70°W 10 links (6.60')

1974 G.F. Dela Mater

Recorded Liber 1 of surveys page 230-232
Found Iron

1975 J.I. Nelson for Mich Con

Recorded L.L.R.C. No. 75-41

No evidence of original witness ties available
Fnd nut bolt 2 ft. below asphalt raised with 5/8" rebar with RLS cap No. No physical evidence going along old fence & tree line going East & corner lies in c/l of Big Four Rd (20' Asphalt)

- 3.) Set Nail w/RLS tag N side 24" Maple Az 88° 34.37'
4.) Set Nail w/RLS tag E side P.Pole AZ 196° 133.71'
5.) Set Nail w/RLS tag NE side 18" Poplar AZ 319° 96.81'

1990 A.M. Slawinski

Recorded Liber 2 of Surveys page 146
No object or references given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On April 27, 1999, I found a 5/8" x 18" rebar over a 12" dock spike and over a stove leg top. No conflicting evidence of other corners existing.

- 1.) & 2.) are now extinct
3.) 24" Maple Az 88° 34.37' Found Nail w/RLS tag N. side
4.) P.Pole AZ 196° 133.71' Found Nail w/RLS tag E side
5.) 18" Poplar AZ 319° 96.81' Found Nail w/RLS tag NE side
A substantial fence line is running to the East from this corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On July 14, 1999, I placed a standard Manistee County Monument within a monument box at the exact position of the above 5/8" iron and is accepted as a careful and faithful perpetuation of the position of the original corner and witnessed by:

- 3.) 24" Maple Az 88° 34.37' Found Nail w/RLS tag N. side
5.) 18" Poplar AZ 319° 96.81' Found Nail w/RLS tag NE side
7.) 14" W. Pine S54°W 69.65' Set 60-D spike S. side
4.) P.Pole AZ 196° 133.71' Found Nail w/RLS tag E side
6.) 10" R. Pine S52°E 55.04' Set 60-D spike S. side

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date 9-16-99

ratified by the Manistee County Peer Group
Corner M-06
according to the county plan adopted pursuant to P.A. 345 of 1990,
as amended, (being the State Survey and Remonument Act, MCL 54.261
at sec. ) . Date of Peer Review: Sept 7, 1999