

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Manistee (County)

Located In: Corner Code ##

- 1. Public Land Survey T23N R16W G-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REGISTER'S OFFICE MANISTEE COUNTY #93-584 AT 11:45 A.M. OCT 6 1993

Fenny A. Ferraro REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 2.

I, Richard Hays, in a field survey on September 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1 CLOSING CORNER COMMON TO SECTIONS 03 & 04 G.L.O. 1839 10" Beech S 56° E 61 LK 12" Beech S 73° W 32 LK Stream at 79.70 ch 6 LK SW 76 or 96 LK East of Post

Plat of Hopkins Addition 1883 (show corners - no witness) Chas. Dodt in early 1960's (no witness) 1972 Anthony Slawinski found 1 1/2" sq. Iron and 3/4" pinched pipe 63.05 West possible from Dodt work (no Witness)..

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 CLOSING CORNER COMMON TO SECTIONS 03 & 04 1993: Found 1-1/2" Sq. Iron Axle and 3/4" Pinched Iron Pipe 63.05' West. Corner fits G.L.O. Stream Call (240 ch or 26.4) - measured 21' and old fence line South. Also Stream call for the SE corner of 33 checks with location of 3/4" pipe found.

Corner G-1 CLOSURE CORNER ratified by the Manistee County Peer Group pursuant to P.A. 123 of 1915, as amended by P.A. 345 of 1990, as amended. Date of Peer Review: APPROVED OCT 4 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 CLOSING CORNER COMMON TO SECTIONS 03 & 04 Replace 1-1/2" Sq. Iron Axle with Standard Manistee County Monument with Brass Cap as a careful and faithful re-establishment of the position of the Original Corner ( 0.09' below Drive) with the following Witnesses: 17" Cedar N-78°-E 78.61' 12" Maple S-30°-E 40.28' NE Cor. Headwall(6'X0.5') S-10°-E 15.00' 6" Maple S-35°-W 95.32' SE Cor. Sec. 33(Co. Mon.) West 63.05' Driveway North 4.0' Old Fence Line to the South

Signed by Richard Hays Date Sept 30 1993

Surveyor's Michigan License No. 25847