

OCT 3 1 1994

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Manistee
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>23N</u> R <u>16W</u> | <u>K-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

REGISTER'S OFFICE
MANISTEE COUNTY

#94-446 AT 10:40 A.M.
SEP 29 1994

Bonny A. Pezner
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Bruce J. Jenema, in a field survey on August 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


JAMES HIGHBY 1834

A. Description of original monument and accessories and/or subsequent restoration:

one-quarter corner common to Sections 23 and 24, T23N, R16W
K-8 ~~one-quarter post between 23 and 24~~ Beech 14" N70°E 32 links
Beech 12" N79°W 14 links
1909 E.W. Manchester Witnesses: W. Pine stump 41" N22 3/4°W 105 1/2 links
W. Pine stump 36" S20°E 166 links
Book A Page 234, Book A page 235 Establish midway and on line
EW Manchester 1908 Act. 74, 1970 #82-5

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 8, 1994 Found railroad Spike



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced railroad spike with Manistee County Monument (2 1/2"x30" steel pipe with a brass cap) placed in a monument box and is accepted as a careful and faithful re-establishment of the position of the original corner and witnessed by:
utility pole N90°W 32.75' 14" Oak S45°E 83.51'
Guide pole S85°E 22.82' 14" Mulberry S23°W 113.76'

Corner K-28 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Hauwala
APPROVED SEP 12 1994

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date 9-8-94