

OCT 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Manistee

(County)

Located In:

Corner Code #

- |                                    |   |     |   |     |     |
|------------------------------------|---|-----|---|-----|-----|
| 1. Public Land Survey              | T | 23N | R | 16W | K-9 |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
|                                    | T |     | R |     |     |
| 2. Property Controlling in Section | S |     | T | R   |     |
|                                    | S |     | T | R   |     |
| 3. Miscellaneous Property in Sec.  | S |     | T | R   |     |
|                                    | S |     | T | R   |     |

REGISTER'S OFFICE  
MANISTEE COUNTY

#94-447 AT 10:43 A.M.  
SEP 29 1994

*Penny A. Pappas*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bruce J. Jenema, in a field survey on August 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to Sections 23,24,25,26 T23N,R16W  
K-9 1839 James Highbee GLO Surveyor Post Sections 23,24,25,26  
Beech 14" N70°E 20 links Hemlock 24" N25°W 18 links  
1913 E.W. Manchester Iron corner post S42°E 62 links Gas pipe set by Knight  
Book A page 234  
Certificate of survey recorded Liber 1 of surveys page 577 Norlund & Dunlap  
Witness: N35°E 45.94' P. Pole  
S30°E 111.57' 16" Maple 1/2" iron pipe N40°W 45.07'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x12" iron pipe at the road surface, 14" below the road surface  
found 1 1/4" iron pipe surrounded by cobbel stones, remains of wooden stake  
and 1"x1/8" iron strap



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed Manistee County Monument (2 1/2"x30" steel pipe with a brass cap)  
over the 1 1/4" pipe, replaced cobbel stones and accepted as a careful and  
faithful re-establishment of the position of the original corner and  
witnessed by: Transformer pole N35°E 45.37' 6" B. Locust S50°W 66.46'  
Transformer pole N40°W 45.10' 20" S. Maple S20°E 112.32'  
Mrs. Jas. Murphy Head Stone S60°E 98.40'

Corner K-9 ratified by the Manistee County Peer Group  
according to the county plan adopted pursuant to P.A. 345 of 1990,  
as amended, (being the State Survey and Remonument Act, MCL 54.261  
et. seq.). Date of Peer Review: Anthony M. Hawnicki

APPROVED SEP 12 1994

Signed by Bruce J. Jenema  
Surveyor's Michigan License No. 25850

Date 9-8-94