

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee (County) Located In: Corner Code #
1. Public Land Survey T 23NR 16W M-02 E 1/4 cor. Sec. 1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY
98-376 at 10:45am
SEP 17 1998
Deborah Dix
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell (2, L) contains a dot.

I, Bruce J. Jenema, in a field survey on April 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not established by the original government survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found P.K. nail 11.40 ft. South of the W 1/4 corner of Section 6, T23N, R15W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On August 1, 1998, I set a standard Manistee County Monument within a Monument Box in the exact location of above P.K. nail and is the best available evidence of the location of this corner and witnessed by:
(1) N75°E 30.85' P.pole 60-D N. side
(2) S34°W 89.45' 8" Cherry 60-D E. side
(3) N55°W 58.28' 14" R. Pine 60-D S. side
(4) N30°W 74.18' 16" W. Pine 60-D S. side
(5) North 11.40 ft. W 1/4 corner, Section 6, T23N, R15W
Corner M-02 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.) . Date of Peer Review: Anthony M. Slawski

AUG 04 1998

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date AUG 3 1998

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 197

REVISED MAY 14, 197
REVISED JAN., 1983
REVISED OCT., 1996

