

MAY 16 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Manistee
(County)

Table with columns: Located In: (T23N R 16W), Corner Code # (M-05 SE Sec. 12), and STANDARD.

REGISTER'S OFFICE
MANISTEE COUNTY
96-461 at 3:00pm
OCT 16 1996
Deborah Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13.

I, Bruce J. Jenema, in a field survey on September 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-05 SE corner Section 12, T23N, R16W
John Brink 1836 Set post 12 & 13
(1) 11" Beech S27°W 44 links (2) 11" Beech N51 1/2°W 48 links
E.W.M. 1893 Book "A", page 234
(3) Illegible 12" S84°E 183' (4) 6" Cedar Post N48°W 66'
Set stone by Testimony of Trobridge 1915 E.W.M. Found stone


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 60-D spike for closing corner between Section 7 & 18, T23N, R15W and established M-05 18.66' South between Northwest corner of Section 18 and the Southwest corner of Section 18, using the information from Book "A", page 234. Occupation line extends West from this position of the corner.

Corner M-05 STANDARD ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Reorganization Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 17 1996
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On Sept. 17, 1996, I installed a standard county marker within a monument box as a careful & faithful re-establishment of the position of the original corner and witnesses by:
(5) Guy pole S75°W 46.0' #16 nail & washer
(6) 8" Cottonwood 51.35' Set 60-D South face
(7) 8" B. Locust 82.65' Set 60-D South face
(8) 14" Cottonwood 62.25' Set 60-D South face
(9) Closing corner between sections 7 & 18, T23N, R15W, 18.66' North



Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date Sept. 17, 1996