

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Manistee
(County)

Table with columns: Located In: (T 23N R 16W), Corner Code # (M-07 SE Sec. 13), and STANDARD.

REGISTER'S OFFICE
MANISTEE COUNTY
96-463 at 3:10pm
OCT 16 1996
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13.

Bruce J. Jenema in a field survey on September 9, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-07 SE corner Section 13, T23N, R16W
John Brink Deputy Surveyor 1839
(1) 11" Beech S27°W 44 links (2) Beech N51 1/2°W 18 links
March 1889 Cook Found stake and witness stump Set stake
(3) 10" Maple N41 1/2°W 35 ft. (4) 7" Maple S73°W 36 1/6 ft.
Witnesses now extinct.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On September 22, 1995, a survey was prepared in the NE 1/4 of the NE 1/4 of Section 24, T23N, R16W, by Bruce J. Jenema. A 1/2" iron bar was set 18' South of the SW corner of Section 18, T23N, R15W and on the West line of Section 19 for M-07 and witnessed by:
(5) Manistee County Marker closing corner North 18.0'
(6) 30" Maple N54°E 48.42' (7) 24" Maple N68°E 73.63'
(8) P.Pole S71°E 44.80' (9) 8" R. Pine S61°W 50.45'

Corner M-07 STANDARD ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monument Act, MCL 54.261 et. seq.). Date of Peer Review SEP 17 1996 Anthony M. Nowinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On September 9, 1996, I installed a Manistee County Monument, within a monument box in the exact location of the above 1/2" iron rod and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by: Witnesses (5), (6), (7), (8) & (9) were found in good condition.
(10) 40" Maple S16°E 120.09'

Signed by Bruce J. Jenema
Surveyor's Michigan License No. 25850

Date September 9, 1996

