

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Manistee

SECTION

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|------------------------|
| 1. Public Land Survey | T <u>23N</u> R <u>16W</u> | M-09 SE Sec. <u>24</u> |
| | T _____ R _____ | STANDARD CORNER |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

REGISTER'S OFFICE
MANISTEE COUNTY

96-466 at 3:25 PM
OCT 16 1996

Deborah Sui
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Bruce J. Jenema, in a field survey on September 16 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-09 SE corner Section 24, T23N, R16W.
 John Brink, Deputy Surveyor 1837
 (1) 18" Hemlock S39°W 49 links (2) 10" Hemlock N62 1/2°W 60 links
 Original surveyor (Highbee) closing corner is 30 links South, now extinct
 June 23, 1913 Iron rod set by Millard (3) W. Pine stp. S72 1/2°W 62 links
 Witness now extinct
 L.C.R.C. #74-8 by Joe Berryman Witnesses, (A-09)
 The closing corner, and as witnesses indicates a 4" concrete monument South 19.88' which compares to the GLO calls of (19.80').

Corner M-09 STANDARD related by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Monumentation Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 17 1996

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: *Anthony M. Stankovic*
 On September 9, 1996, I found a concrete monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 On September 9, 1996; I accepted the concrete monument as a careful & faithful re-establishment of the position of the original corner and took the following witnesses:

Road construction will not permit the installation of a permanent County monument at this time. As soon as conditions permit I will install the permanent monument in the exact position as the above concrete monument. (monument installed 10/15/96)

- (4) 12" Maple S66°W 59.11' Found nail NW face
- (5) 10" Poplar N22°W 140.66' Found boat spike
- (6) 14" Oak N24°E 108.38' 60-D SE face
- (7) 10" Oak S44°E 94.53' 60-D NE face
- (8) closing corner (A-09) North 19.88'

Signed by *Bruce J. Jenema* Date September 9 1996
 Surveyor's Michigan License No. 25850

