

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Manistee</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>23N</u> R <u>16W</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
*#97-355 At 11:10 A.M.*  
**JUL 25 1997**  
*Penny A. Repora*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Bruce J. Jenema, in a field survey on May 01, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-11 SE corner Section 25, T23N R16W  
 John Brink 1837 North on East side of Section 36, 79.0 chains stream, 80 chains set post (1)10" Beech N32°W 42 links (2)10" Beech N69 1/2°W 22 links  
 Stream 66' South of this corner seems quite reasonable even though road construction has altered the course.

**SURVEY &  
 REMONUMENTATION**  
**OCT 14 1997**  
**COMMISSION**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 5/8" rebar at surface of road.  
 The North line of the Plat of Shimpkey's Addition, which is the North line of Section 31 extended West would match this location.

Closing corner between Sec. 30 & 31, T23N, R16W is 16.5' South

Corner M-11 certified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 346 of 1990, as amended, (being the State Survey and Monumentation Act, MCL 54.261 et. seq.). Date of Peer Review: MAY 6 1997 *Arthur M. Hawick*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

On May 02, 1997, I installed a Manistee County Monument, within a monument box in the exact location of the above 5/8" iron and is accepted as a careful & faithful re-establishment of the position of the original corner and witnessed by:  
 (3) 1.5 sq. concrete marker SE corner N38°W 50.08'  
 (4) Telephone Pedestal N57°E 52.52'  
 (5) 14" Elm S12°E 89.50' 60-D N.side  
 (6) Utility pole S31°W 64.29' Found #16 spike/washer W.side



Signed by Bruce J. Jenema  
 Surveyor's Michigan License No. 25850

Date May 02, 1997