

DEC 6 9 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Manistee County (County) Located In: Corner Code #
1. Public Land Survey T 24N R 13W H-13
South 1/4 Cor.
Sec. 34
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

REGISTER'S OFFICE MANISTEE COUNTY
99-318 at 11:20AM
SEP 23 1999
Deborah Dix
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Anthony M. Slawinski, in a field survey on August 19, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-13 South 1/4 Corner Section 34, T24N, R13W

- Set by John Brink in 1838
1. Beech 13" dia. N 55° E 55 links (36.3') (Gone)
2. Beech 8" dia. N 04 1/2° W 30 links (19.8') (Gone)

- Survey Certificate by James Ray (1987)
Found 1/2" Iron in C.L. of road
3. South 37.02' Corner of fence post (Gone)
4. North 42.41' 24" Maple (Good)
5. S 30° W 45.23' 28" Cottonwood (Gone)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13 South 1/4 Corner Section 34, T24N, R13W

On August 19, 1999, I, Anthony Slawinski, with a crew from Abonmarche found a 1/2" Iron rod in a Monument Box in the centerline of 13 Mile Road. I found no other evidence to dispute this location for the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13 South 1/4 Corner Section 34, T24N, R13W

On August 19, 1999 I installed a Manistee County Monument, within a monument box, in the exact location of the above mentioned 1/2" iron rod as a careful and faithful re-establishment of the position of the original corner and witnessed by:

- 4. N 02° E 42.46' 30" Maple found 60D flush to the East side of tree, set a new 60D spike in the East side of tree
6. N 60° W 85.60' 4" Black Walnut, set 60D spike in East side of tree
7. S 04° W 89.10' Power Pole, set 60D spike in East side of pole
8. S 48° W 99.65' 6" Jack Pine, set 60D spike in West Side of tree

Note: Corner is in the center line of 13 Mile Road.
Note: Tree line and remains of old fence to the North of Corner.

Grid table with columns A-M and rows 1-13. A dot is marked at row 13, column H.



Corner H-13 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 07 1999 Anthony M. Slawinski

Signed by Anthony M. Slawinski Date 9-7-99
Surveyor's Michigan License No. 13597