

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Manistee Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T	24N	R	13W	B9	
	T		R			
2. Property Controlling in Section	S	T	R			
	S	T	R			
3. Miscellaneous Property in Section	S	T	R			
	S	T	R			

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on April 17, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B9 – GLO – Set ¼ Post – John Brink – 1839  
 Balsam 8" S87°E 12 L.  
 Balsam 8" S12°W 14 L.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

B9 – ¼ Corner common to Sec. 19 & 30 – Could find no evidence of original corner or witnesses. Set 1" x 5' long galvanized iron pipe with a stamped 4" DNR Aluminum cap, single proportion to GLO. Monument is in Fir, Maple, Ash & Cedar swamp. DNR monument is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B9 – 4" DNR Aluminum cap on 1" x 5' long galv. iron pipe – up 1'  
 N71°E 31.08' to set N & T in N. side 7" R. Maple scribed "XBT"  
 N19°E 23.35' to set N & T in W. side 7" Basswood clump of 5 scribed "XBT"  
 S3°W 46.87' to set N & T in E. side 8" Cedar scribed "XBT"  
 N66°W 37.17' to set N & T in NE side twin 8" E. Maple scribed "XBT"  
 Set Blue Carsonite Post 1' North



Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 1/25/2007