

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Manistee Located In _____ Corner Code # _____
(County)

1. Public Land Survey T _____ R _____
T _____ R _____

2. Property Controlling in Section S 20 T 24N R 13W 10
S 20 T 24N R 13W CWSW 1/64

3. Miscellaneous Property in Section S _____ T _____ R _____
S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on Sept. 13, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

10 - None CWSW 1/64 - None



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

10 - S 1/16 Corner common to Sec. 19 & 20 - Fd. Mag. Nail - 0.5' W. of centerline N-S Bit. Rd. Mag. nail accepted as the best available evidence of the position of the corner. CWSW 1/64 - being the NE Cor. of W 1/2 of SW 1/4 of SW 1/4, Sec. 20 - Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10 - Replaced Mag. Nail w/ stamped 2" Alum. Cap on 5/8" x 24" rebar flush w/ Bit. Rd. East 33.07' to Fd. 1/2" CIR #25845 and add Blue Carsonite Post w/ loc. tag N87°W 45.56' to set N & T in N. side 27" W. Pine S53°W 53.15' to set N & T in SE side 30" W. Pine N50°W 52.59' to set N & T in NE side 21" Hemlock CWSW 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" rebar. Set Blue Carsonite Post w/ loc. tag 1' SW S47°E 20.40' to set N & T in NE side 5" Fir S5°E 28.74' to set N & T in E. side 5" Fir S50°W 26.20' to set N & T in SE side 6" S. Maple N25°E 11.01' to set N & T in NW side 3" R. Maple

Signed by: Craig W. McVean Date: 1/25/2007
Surveyor's Michigan License No.: 39088