

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Manistee Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey	T _____	R _____			
	T _____	R _____			
2. Property Controlling in Section	S <u>29</u>	T <u>24N</u>	R <u>13W</u>		<u>2</u>
	S <u>20</u>	T <u>24N</u>	R <u>13W</u>		<u>WW 1/64</u>
3. Miscellaneous Property in Section	S _____	T _____	R _____		
	S _____	T _____	R _____		

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on Sept. 14, 2006 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 2 - Rec. Survey - L. 1 of Surveys, p. 314 - G. F. DeLaMater - WW 1/64 - None  
 1976 - Iron set
- Rec. Survey - L. 3 of Surveys - P. 258 -  
 D. G. Heydlouff - 2004 - iron found



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 - E 1/16 Common to Sec. 20 & 29 - WW 1/64 - Corner common to Sec. 20 & 29  
 Set stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM Procedure  
 Centerline 2-track - E & SW is 50' South. Old Field line South.
- Reference Pt. - N75°15'E 4.06' of "2"  
 Fd. 1/2" capped iron (Number unreadable) that fits Record Surveys per Part 'A'. Couldn't accept this 1/2" CIR since it is based on rejected position for 'D9'.
- WW 1/64 - Being the SE Cor. of the W 1/2 of the SW 1/4 of the SW 1/4 of Sec. 20 - Set Stamped 2" Alum. Cap on 5/8" x 34" rebar per Standard BLM Procedure

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2 - Stamped 2" Alum. Cap on 5/8" x 34" rebar  
 Set Orange Carsonite Post w/ loc. tag 1' NW  
 S32°W 76.21' to set N & T in NW side 18" S. Maple  
 S68°W 38.06' to set N & T in S. side 27" Tri. S. Maple  
 N13°E 25.46' to set N & T in W. side 6" Cherry  
 N79°E 124.47' to set N & T in S. side 20" Tw. Cherry
- WW 1/64 - Stamped 2" Alum. Cap on 5/8" x 34" rebar  
 Set Blue Carsonite Post w/ loc. tag 1' SW  
 North 4.89' to set N & T in W. side 8" Spruce  
 N82°W 9.24' to set N & T in N. side 15" Cedar  
 S39°W 21.68' to set N & T in SE side 6" Y. Birch  
 N38°E 10.16' to set N & T in E. side 10" Cedar

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 1/25/2007