

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 14W


Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 21-28

CORNER MONUMENT 1" pipe with aluminum cap 6" below surface

DATE MONUMENT PLACED AND WITNESSED 11-2-61

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" Cherry - N 29 W - 57.3 feet

Apple Tree - S 52 W - 61.8 feet

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was established while making a survey in this township. Unable to locate any previous corner in cut section of E-W road. Set corner in centerline of E-W road at Muenscher's record measurement from E 1/8 corner between 21-28, which also checks the record measurement west to W 1/8 between 21-28, and falls on line with 1/8 and section corner east and west. This method presumes to restore the corner as established in Muenscher's 1907 survey.

**SURVEYOR'S SEAL**

SIGNED *Leventh J. Ostling* DATE 11/15/61  
REGISTERED LAND SURVEYOR