

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 14


Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28-29

CORNER MONUMENT Set 1" pipe with aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-1-61

WITNESSES TO CORNER.....



48" W. Pine Stump - S 82 E - 61.0 feet

10" Cherry - N 7 W - 9.9 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored while making a survey in this area. Set corner from probable remains of pine stump new bearing tree noted by E. W. Muenschler in a 1907 survey. Corner falls in a Hemlock stump bottom, which was concluded to be the original corner tree. Falls in E-W fence line and appears to be the best available evidence of proper location for corner.

SURVEYOR'S SEAL

SIGNED *Renneth J. Oetting* DATE 11/15/61
REGISTERED LAND SURVEYOR