

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 14


Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28 - 33

CORNER MONUMENT Set 1" x 24" pipe on top of 1" pipe in place

DATE MONUMENT PLACED AND WITNESSED 11-1-61

WITNESSES TO CORNER.....



4" W. Pine - S 49 E - 59.2 feet

\* 40" W. Pine Stump - S 54 W - 60.7 feet

AND  
Power Pole - N 47 E - 52.3 feet

\* Muenscher new bearing tree

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was found while making a survey in this township. Found a 1" pipe buried 2 feet below surface of road as restored by E. W. Muenscher in 1907 survey of Section 28. One new bearing tree in place. Falls nearly in line with fence north, and about 3 feet north of centerline of E-W road. Records would indicate this is a restoration of original corner.

**SURVEYOR'S SEAL**

SIGNED *Kenneth Ostling* DATE 11/15/61  
REGISTERED LAND SURVEYOR