

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N. R. 14W


Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28-29-32-33

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 11-1-61

WITNESSES TO CORNER.....



14" Cherry - N 85½ E - 112.6 feet

18" Twin Maple - S 17 E - 95.1 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this township. Could not identify Kuenschler's new bearing trees or U.S. bearing trees. Set corner on line over, and equidistant from 1/8 corner and 1/4 corner east. This point falls in line with fence north, but is about 45 links south of E-W fence. Conforms closely to measurements of record to 1/4 corner north and section corner south. Considered this an acceptable restoration of Kuenschler's 1907 corner.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostberg DATE 11/15/61  
REGISTERED LAND SURVEYOR