

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 24 N.R. 14 W


Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 16-21

CORNER MONUMENT 1" x 24" pipe

DATE MONUMENT PLACED AND WITNESSED \_\_\_\_\_

WITNESSES TO CORNER..... 11-2-61



10" Cherry - N 27 W - 60.0 feet

12" Elm - N 59 E - 90.0 feet

AND \_\_\_\_\_

CIRCLE CORNER REGISTERED

### DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this township. Unable to locate anything for a previous corner or new bearing trees. Set corner on line between section corners, at Millard's record measurement for east 1/2 mile of 40.46 chains. This checks east 1/8 line fence and falls about 3 feet south of apparent center-line of E-W county road at this point.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE 11/15/61  
REGISTERED LAND SURVEYOR