

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 14W


Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21-22-27-28

CORNER MONUMENT Drove 1/2" x 14" iron bar thru blacktop

DATE MONUMENT PLACED AND WITNESSED 11-2-61

WITNESSES TO CORNER.....



Concrete Road Marker - S 57 E - 51.8 feet

Power Pole - N 24 E - 144.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey in this township. Unable to locate any previous corner in what appears to be a fill section of N-S county road. Set corner in line with apparent centerline of old road west, at Muenscher's record measurement from E 1/8 corner between 21-28. This falls on west edge of N-S blacktop, but checks the record of restored 1/4 corner west; also checks measurements to fence lines south and measurement of record north.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11/15/61
REGISTERED LAND SURVEYOR