

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 14 W.

Manistee

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 13 and 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Cedar - S50E - 29 1/2 links

8" Cedar - S47W - 47 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners, by Forestry Division survey crew while making a survey in this area. Unable to identify government BTs, but corner checks very well with swamp edges east and west.

Corner set and witnessed December 16, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting
REGISTERED LAND SURVEYOR

DATE 12/27/60