

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 14 W.

Manistee

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 15 and 22

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

4" J. Pine - N51W - 66½ links

13" H. Maple - S19E - 13½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by Proportionate measurement, midpoint on line, between section corners, by Forestry Division survey crew while making a survey in this area. Unable to locate any previous corner. Corner falls about 3 links east of fence line south and approximately in line with road west.

Corner was set and witnessed December 16, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/27/60