MICHIGAN DEPARTMENT OF CONSERVATION

FORESTRY DIVISION

LAND CORNER RECORD

T 24 NR 14 W

	Maniet	69 COUNTY
DESCRIPTION OF CORNER	Section corner common t	o Sections 14-15-22-23
DESCRIPTION OF CORNER MONUMENT I pipe with 4" brass cap		
WITNESSES TO CORNER		
	5" Cedar - N16E	- 28 links
	5" Cedar - N44W	- 38 links
	24 dedar stump - 842E	- 57 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Divisiom survey crew while making a survey in this area. Set this corner by proportionate measurement between corners 1 mile west and 2 miles east for longitude, making each mile 6 links longer than record. For latitude, corner was set at record measurement south of marsh edge, which would conform to location for 1/4 between 14 and 15. There is also an error in the government survey (or in the later restoration of the corner to Sections 10-11-14-15) which is very obviously in the north 1/2 mile between 14 and 15. Did not believe this error should be carried into other sections. Longitudinal position checks very good to stream crossing east, and placed 1/4 corner west very nearly in conformity with old fence line south. This action seemed most in line with the government record.

Corner was set and witnessed December 16, 1960.

SURVEYORS SEAL

SIGNED LEMENT DATE 12/27/6