

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 14 W.

Manistee COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 22-23-26-27

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" B. Ash	-	N40W	-	13 links
12" B. Ash	-	S47W	-	37½ links
8" Elm	-	N88E	-	8½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this township. Set corner by double proportionate measurement between corners 1 mile west, 2 miles east, 1 mile south and 1 mile north. Unable to identify anything for government BTs.

Corner set and witnessed December 16, 1960.

SURVEYORS SEAL

SIGNED *Kenneth A. Oetting*
REGISTERED LAND SURVEYOR

DATE 12/27/60