

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 14 W.

Manistee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 26 and 35

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

12" S. Maple - S67W - 129 1/2 links

9" S. Maple - S7E - 64 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in this area. Do not believe this corner was originally set since government notes call for Cedars in high, dry land with Maple and Cherry cover. Falls in line with road west and parts of road north.

Corner was set and witnessed December 15, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Oetting DATE 12/27/60  
REGISTERED LAND SURVEYOR