

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 NR. 14 W.

Manistee

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 25 and 26

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

36" W. Pine stump - N54E - 74 links

36" W. Pine stump - S41E - 101½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between section corners, by Forestry Division survey crew while making a survey in this area. Could not locate or identify corner of record by E.W.M. in 1915, or the government BTs. Corner falls about 20 links north of E-W- 1/4 line road.

Corner was placed and witnessed December 15, 1960.

SURVEYORS SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 12/27/60