

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 .. NR. 14 W ..

Manistee

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13-14-23-24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

9" Cedar stump - N79E - 53½ links  
14" W. Pine stump - N30W - 43½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey in this area. Set this corner by proportion between corners 2 miles west and 1 mile east for longitude, making each mile 6 links longer than government. Corner was set for latitude to conform to two swamp edges north and section corner three miles south, making these three miles 5 links short per mile. Although we cannot identify the government BTs, this is the only point that conforms to the calls of the government record. Corner had to be this far south to check swamp edges about 6 and 15 chains north, as well as at 42 chains north; also, to stay in swamp going east. Longitudinal position considered very good since it checks with stream crossing west and swamp edges east. Error in government measurement (or in later survey) can most satisfactorily be isolated in north 1/2 mile between 13 and 24, and did not believe this 2.50 chain over-run should be reflected in all the sections to the south. Considered this solution most in conformity with the government record.

SURVEYORS SEAL

Corner placed and witnessed December 15, 1960.

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 12/27/60