

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24. NR. 14. W.

Manistee

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 25-26-35-36

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

8" Poplar - S19W - 9½ links

8" Maple - N41E - 73 links

7" Maple - N78W - 75 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by double proportionate measurement between section corners 2 miles north, 1 mile south, 1 mile east, and 1 mile west, by Forestry Division survey crew while making a survey in this township. Cannot identify government BTs.

Corner was placed and witnessed December 15, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 12/27/60