

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T 24 NR 14 W

Manistee

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 23-24-25-26

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

10" B. Cherry - S51W - 75½ links

18" B. Cherry - S72E - 76½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile north, 2 miles south, 1 mile east and 2 miles west, by Forestry Division survey crew while making a survey in this township. Error in government notes calls for this corner in swamp, but nearest swamp is 1/4 mile north. Do not believe this corner was ever set in original survey.

Corner was placed and witnessed December 15, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 12/27/60