

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T $\frac{24}{24}$ NR $\frac{13}{14}$ W
T 24 NR 14 W

Manistee

COUNTY

DESCRIPTION OF CORNER $\frac{1}{4}$ corner common to Sections 19 and 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

18" B. Cherry	-	S30W	-	131 links
4" R. Pine	-	S48E	-	84 $\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew while making a survey in T24NR14W. Government evidence all gone.

Corner was placed and witnessed December 14, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* - DATE 12/27/60
REGISTERED LAND SURVEYOR